

TECHNICAL SPECIFICATION FOR SUPPLY, TRANSPORTATION, INSTALLATION & COMMISSIONING OF 180 KVA DIESEL GENERATOR SET 01 NO. CUMMINS / KIRLOSKAR MAKE FOR FUNCTION HALL AT MINI SHILPARAMAM, UPPAL

Sealed Quotations should be submitted at **Shilparamam, Madhapur Office** on or before **18.01.2023 up to 4:00 PM** in Favour of

SPECIAL OFFICER  
SHILPARAMAM  
HYDERABAD

SNo	Particulars	Qty	Unit	Rate	Amount Rs
1	Supply, Installation & Commissioning of <b>180 KVA, 415 Volts Silent DG Set</b> comprising of <b>Cummins / Kirloskar / Green make</b> Engine developing 234 BHP, 144 KW with all standard meters and accessories coupled to <b>Alternator Stamford / Kirloskar make</b> 180 KVA, 3 Phase self-excited, self-regulated, rated at 415V, 50 Hz, 1500 RPM, 0.8 P.F. mounted on a common base frame, complete with: a) Fuel Tank, b) Batteries & Leads, c) Silencer – Residential, d) AVM Pads, e) First fill of Lube Oil, f) Acoustic Enclosure	1	No		
2	AMF Panel with double contactors for EB Supply & DG Supply suitable for one EB Meter	1	No		
-	<b>Sub Total</b>				
	GST @ 18%				
	<b>GRAND TOTAL AMOUNT RS</b>				

Note:

1. Due to variation of Load, earlier proposed 125 KVA Generator is amended. Hence, instead of 125 KVA **we are going for 180 KVA.**
2. The rates should be quoted separately for both Generator & AMF Panel.
3. The Transportation & Unloading of DG Set is in firm scope.
4. After Confirmation of Order, The Advance Payment shall be released @ 80% and Balance Payment will be released after successful completion of work.

  
A.E/Elec

  
E.E/Elec